

## CAPITOL ENGINEERING LABORATORIES, INC.

Materials Testing • Inspection • Crane Certification

File No. 5533 June 18, 2002

Chris Sullivan Frame Pro Products, LLC 900 Business Park Dr., Suite D Dixon, CA 95620

Project:

Scaffold assembly testing

Subject:

Guardrail post receiver type 2 testing

Dear Chris,

On 6/13/02 I proof load tested one of your sub-floor guardrail post receiver type 2 units. The sub floor guardrail receiver was attached to the vertical face of a  $1-\frac{1}{4}$ " thick truss joist 1.3e LSL rim board using four  $\frac{1}{4}$ " diameter lag screws. The rim joist was installed in a typical construction configuration. The sub floor was screwed to this rim board and the floor joists were perpendicular to rim board.

Testing consist of applying a horizontal outward static load at the center of the upper rail (approx 42" above the floor).

The test load was applied using a cable lever hoist, the load was measured using a calibrated  $500 \, \mathrm{lb}$  dynamometer manufactured by Dillon (S/N 53354). The post receiver sustained a  $200 \, \mathrm{lb}$  static horizontal load with minor evidence of flexing of the double angles (see photos).


Respectfully submitted,

CAPITOL ENGINEERING LABORATORIES, INC.

G. Barry Lotz, C,

061802. 867/kv





Guardrail receiver w/200# horizontal load





Guardrail receiver w/200# horizontal load close-up